

SAFE WORK METHOD STATEMENT			ABN: 96 151 257 582	SWMS NUMBER	SWMS01
Company Details	Campbell Construction Co, Building B 4-6 Innovation Parkway Birtinya QLD			Contact Number	1300 938 040
Project Address				Project No (CCC)	
Date Prepared		Prepared By (Supervisor Name)		Review Date	13/9/2022
SWMS Approved by	Ben Campbell CEO Signature: 			Date	13/9/2021
Person Responsible for SWMS (Supervisor Name)				Contact Number	
WORKING WITH HAZARDOUS SUBSTANCES					
High Risk Construction Work (HRCW)	Is carried out in an area that may have a contaminated or flammable atmosphere				
Implementation, Monitoring and Review of the SWMS	WHSE Inspections, WHSE Internal Audits, Toolbox Talks				
Action taken prior to work commencing	Ensure an SDS for the chemical is available, Ensure PPE is available and suitable as per the SDS, inspect work area and ensure it is safe and establish exclusion zones if applicable				
Worker qualifications /experience required for task	General Construction Induction Card, Apprentices/Young Workers need to be supervised at all times and should not work alone				
Personal Protective Equipment requirements	       				

LIKELIHOOD	CONSEQUENCE				
	1 Insignificant	2 Minor	3 Moderate	4 Major	5 Catastrophic
	No Injuries Low financial loss	First Aid, property or environmental damage up to \$2,500	Lost Time Injury, short term temporary disability (< 1 month), property or environmental damage \$2,500 - \$25,000	Lost Time Injury long term temporary disability (>1 month), property or environmental damage \$25,000 - \$250,000	Fatality, permanent disability, property or environmental damage over \$250,000
Almost Certain Expected to occur in most circumstances (<i><monthly</i>)	H	H	E	E	E
Probable Could happen regularly (<i>monthly-yearly</i>)	M	H	H	E	E
Possible Might happen at some time (<i>yearly-3 yearly</i>)	M	M	H	H	E
Unlikely Could happen rarely (<i>3 yearly-10 yearly</i>)	L	M	M	H	H
Very Unlikely Could happen, but probably never will (<i>>10 yearly</i>)	L	L	M	M	H

Risk Action Levels	
EXTREME	Immediately stop the task. Construction and WHS Manager decision required. Inform CEO
HIGH	Task can commence, continually monitor and review controls to ensure ALARP
MEDIUM	Task can commence, controls measures potentially adequate
LOW	Task can commence, controls are adequate

Job Steps	Hazards	L	C	R	Controls	L	C	R	Person Responsible
Handling and Storage	Contact with chemicals due to packaging being damaged and/or not transported safely	PO	3	H	All hazardous substances to be delivered in unopened and undamaged packaging All hazardous substances to be stored, segregated and handled in accordance with the SDS When travelling with hazardous materials appropriate steps should be taken to protect the contents preventing damage to packaging/containers Hazardous substances to be stored only in the approved packaging/containers designed for them All hazardous substances must have a readable label on the container, bottle etc that they are stored in. Writing on a container with a black marker shall not be done	UN	3	M	Site Supervisor Workers
Using Hazardous Chemicals HRCW	Worker unaware of controls causing incorrect use	PO	3	H	All workers read the SDS before the chemical is used Use PPE identified in this SWMS and SDS Workers trained in the handling and use of Hazardous Chemicals, conducted by the supervisor in conjunction with the SDS Consider Substitution of the substance to a non-hazardous one	UN	3	M	Site Supervisor Workers
	Unknown chemicals on site and inaccessible records	PR	3	H	A site chemical register must be completed, kept onsite and accessible to all workers and updated whenever new chemicals come to site	UN	3	M	Site Supervisor Workers
	Chemical contact with skin causing skin irritation, burns	PR	3	H	Worker to wear PPE as identified in this SWMS and the SDS e.g. gloves as necessary etc. Engineering aids e.g. scrapers, caulking guns to be used where possible for application	UN	3	M	Site Supervisor Workers

Job Steps	Hazards	L	C	R	Controls	L	C	R	Person Responsible
					First aid kit on site or in CCC vehicle and first aid trained Personnel Emergency contact list onsite and all workers understand emergency response process through inductions				
	Chemical splashes into mouth causing throat irritation or internal organ issues	PR	3	H	Worker to wear PPE as identified in this SWMS and the SDS e.g. face mask/protection Workers to follow appropriate hygiene standards and wash hands before eating, drinking etc	UN	3	M	Site Supervisor Workers
	Chemical contact with eyes causing eye irritation and potential eyesight issues	PR	3	H	Worker to wear PPE as identified in this SWMS and the SDS e.g. eye protection Workers to follow appropriate hygiene standards and wash hands before eating, drinking etc	UN	3	M	Site Supervisor Workers
	Chemical fumes causing lung irritation and chronic airway issues	PR	3	H	Worker to wear PPE as identified in this SWMS and the SDS e.g. face mask/protection Face mask to be appropriately fitted to ensure no gaps Ensure work area has adequate ventilation e.g. natural or the potential use of mechanical ventilation to remove fumes from work area	UN	3	M	Site Supervisor Workers
	Chemical fumes potential flammable hazard	PR	3	H	Hot works e.g. welding, grinding shall not be conducted around flammable chemicals Implement good housekeeping by ensuring no flammable material is in the work zone Ensure work area has adequate ventilation e.g. natural or the potential use of mechanical ventilation to remove fumes from work area Fire extinguisher onsite and close to Hot Work	UN	3	M	Site Supervisor Workers

Job Steps	Hazards	L	C	R	Controls	L	C	R	Person Responsible
	Other worker potentially exposed to chemicals	PR	3	H	Communication process regarding works to be undertaken e.g. pre-starts, toolboxes Exclusion zones and segregation of works including potential signage	UN	3	M	Site Supervisor Workers
Environmental Considerations	Incorrect disposal causing environmental pollution	PR	3	H	Worker to wear PPE as identified in this SWMS and the SDS until the chemical is no longer being used and is disposed of Dispose of chemical in appropriate site bin Chemicals contact with the ground, ensure the chemical is cleaned up appropriately e.g. spill kit	UN	3	M	Site Supervisor Workers
	Potential public exposure to chemicals once site is shut down	PR	3	H	Ensure site is secured appropriately e.g. temp fence and locked Remove chemicals from site, if chemicals cannot be removed, they shall be locked away and not accessible	UN	3	M	Site Supervisor Workers
Emergency or first aid scenario	Workers unsure of response protocols delaying medical attention	PR	4	E	First aid kit available either onsite or in work vehicle Emergency contact list onsite (<i>where applicable</i>) and all workers understand emergency response process through inductions All workers to know site location/address through inductions for directing emergency services Call 000 or 112 for medical emergencies Emergency evac drills are undertaken	PO	4	H	Site Supervisor Workers
If the job is stopped/or further hazards identified – Document these here									Site Supervisor Workers
									Site Supervisor Workers

Job Steps	Hazards	L	C	R	Controls	L	C	R	Person Responsible
									Site Supervisor Workers
									Site Supervisor Workers
									Site Supervisor Workers

SWMS Sign Off – To be signed by each worker undertaking the task outlined in this SWMS.

I declare that:

1. I have been consulted regarding the content and development of this SWMS
2. I have received all necessary training, instruction and information regarding the contents of this SWMS
3. I have reviewed the task, job steps, hazards and controls and verify I will not carry out the task until all control measures are in place
4. I will stop work and amend the SWMS if any further hazards are identified whilst conducting the task

NAME	POSITION	SIGNATURE	DATE