



Site Safety Rules

All subcontractors and workers on site must ensure the following:

- All incidents, injuries and emergency situations are to be reported to the principal contractor and your supervisor as soon as practicable
- Workers must wear correct personal protective equipment during specific work activities as per manufacturers' recommendations
- Workers are encouraged to wear adequate clothing, sunglasses and sunscreens to protect them from the effects of working in the sun
- Place rubbish in the appropriate rubbish area provided before leaving the site each day
- Work areas to be kept clean and access ways free from hazards at all times
- No alcohol permitted on site unless authorised and supervised by principal contractor
- No illegal substances permitted on site
- Any person affected by alcohol or drugs will not be tolerated and will be denied access to the site
- Toilets are to be used and good hygiene is to be adhered to at all times
- Before using or storing any hazardous substances, a copy of the respective MSDS is to be given to the principal contractor and/or included in the safe work method statements
- All Subcontractors/Suppliers, if necessary, are to have current licences and appropriate skills for the plant and equipment being operated
- No person without specific approval is to alter or remove any plant, equipment or safety device on site. This includes, but is not limited to, scaffolds, handrails, barricades, signage, guards etc.
- Electrical equipment including leads are to be inspected and tagged at intervals not exceeding 6 months and stored in locations where they are not likely to be damaged or create a trip hazard
- Damaged electrical equipment will not be used and is to be removed from site
- No piggyback leads or double adaptors to be used on site, commercial grade power boards only
- Work above 3 metres will require a means of fall protection, work above 2 metres requires a SWMS
- No domestic ladders will be used on site, must be industrial platform ladders and rated at 120kg
- Theft of any kind will not be tolerated and will be reported directly to the police
- All subcontractors are to inform the principal contractor of any unsafe work areas
- All personnel are to be trained in the plant and equipment being used
- All works will be undertaken in an environmentally sensitive manner
- Do not dispose of any substances whatsoever in or near storm water systems or waterways
- No pets permitted on any job sites at any time
- All safety signs are to be complied with in full
- Ensure that the property is always locked up after completion of work
- All Safe Work Method Statements will be adhered to; and
- Workers will adhere to the Principal Contractor Site Rules

I _____ have read and understand the site rules and will ensure compliance on all Watermark Constructions sites.

Signature: _____ Date: _____